



### 133 W. Lincoln Avenue – Contributing (ARC Case 01-08)

This is a two-story, gable front Folk dwelling built in 1910. The house has a brick foundation, an interior brick chimney, a front gable roof of asphalt shingles and an exterior of weatherboard and masonite siding. On the main (N) façade is a single-story, full-width porch rebuilt in 2001 with square wood columns and a square wood baluster railing. The main entrance retains its original, single-light glass and wood door and single-light original storm door. Windows are original, one-over-one double hung rectangular wood sash. The center section of the picture window on the first floor's main façade has a diamond-light patterned transom. In the gable field on the main façade are paired, one-over-one double hung wood sash windows.

Located off the southeast façade is a ca. 1990, frame garage with a gable roof of asphalt shingles, an exterior of weatherboard and a thirty-two metal panel overhead track door. An original, four-light fixed glass and wood window is located in the gable field. - **Noncontributing**

